COUNTY OF SAN JOAQUIN

DEPARTMENT OF PUBLIC WORKS
P.O. BOX 1810-1810 HAZELTON AVENUE
STOCKTON CALIFORNIA 95201
(209) 468-3000
FAX# (209) 468-9324

EP No:	EP-05 103SE
Date Issued:	06/07/2005
Expiration Date:	08/01/2005
Job No:	11005
UE/CR/PM NO:	

ENCROACHMENT PERMIT

To: SAN JOAQUIN COUNTY CAPITAL PROJECTS
100 W. MATHEWS RD.
FRENCH CAMP, CA. 95231

Encroachment Type: FRONTAGE IMPROVEMENTS

Location: N/S MATHEWS RD. FROM MANTHEY RD. FOR 500' WEST, AND W/S MANTHEY RD. FROM MATHEWS RD. FOR 500' NORTH.

In compliance with your request of 6/6/05 permission is hereby granted to do work in County right of way as shown on attached application and subject to all the terms, conditions and restrictions written below or printed as general or special provisions on any part of this form. See reverse side and attached sheet, if any.

Trench excavations for service connections will not be permitted within ten feet (10') of pavement centerline unless otherwise approved by the Director. Surface of trench patches shall match in kind and be smooth and even with that of abutting surface. Special attention shall be given to depth of utilities through roadside area in anticipation of future drainage facilities, road profile and/or frontage development. All underground utility facilities are to be established and accurately dimensioned on sketches from surveyed centerline of road right of way, not from right of way (border) lines.

The Department of Public Works, Field Inspection Section shall receive a notice at least forty-eight hours prior to beginning any work within the County right of way. All work performed under this permit shall conform to the rules and regulations pertaining to safety established by the California Division of Industrial Safety and Cal-OSHA.

The jobsite shall be kept in a safe condition at all times by the daily removal of any excess dirt or debris which might be a hazard to either pedestrian or automobile traffic. All necessary traffic convenience and warning devices and personnel shall be provided, placed and maintained by and at the sole expense of the Permittee in accordance with the latest edition of the CALTRANS Manual of Traffic Control.

After completion of the work permitted herein, all debris, lumber, barricades, or any excess material shall be removed and the jobsite left in a neat workmanlike manner. Immediately following completion of construction permitted herein, Permittee shall fill out and mail notice of completion provided by Grantor.

Special Instructions:

THOMAS R. FLINN, Director
Department of Public Works

Est. Permit Fee: $13,369.00
FORMS: SS/WW, R-29

By _____
Permit Section

WHITE - Permittee
GOLDENROD - PWD Central File
YELLOW - Field Inspection
PINK - Permit Section

PW 27

APPLICATION FOR ENCROACHMENT PERMIT

PLEASE PRINT:

Date 6-6-05

To: San Joaquin County
Department of Public Works

San Joaquin Co. Capital Projects
(Applicant Name)

100. W. Mathews Rd.
(Mailing Address)

French Camp, Ca 95231
(City, State, Zip Code)

(209) 468-4540
(Area Code - Telephone Number)

OFFICE USE ONLY

JOB # 11005 REF #
APN CR #
EXP. DATE 8/1/05
VALID 6/8/05 TO 8/1/05 DRIVEWAYS:
STREET MATHEWS RD., MANTHEY RD
AREA FRENCH CAMP QUAD SE *
TYPE FRONTAGE IMPROVEMENTS *
FORMS SS/WW
NOTE

Sketch (Detailed plans may be submitted)

See attached plans

The undersigned hereby applies for permission to excavate, construct and/or otherwise encroach on County Highway Right-of-Way on the NORTH side of Mathews Rd approximately 500 feet/mile WEST of MANTHEY RD, , by performing the following work (description of work): FRONTAGE IMPROVEMENTS INCLUDING UNDERGROUND WORK FOR HOSPITAL

Work will commence on or about 6/16/05 for approximately 5 days.

I, the undersigned certify that I am the owner of the respective property, or am qualified to represent the owner and agree to do the work described above in accordance with the rules, regulations of San Joaquin County and subject to inspection and approval.

Signature of Applicant - Title

6/6/05
Date

MASTER.PS\FEESCHDL (6/00)

IMPROVEMENT PLAN SUBMITTAL CHECKLIST

A. The following items must be submitted to the Public Works Department before the Improvement Plans can be checked:

1. Preliminary Engineer's Estimate

2. Plan check fee based on the preliminary Engineer's Estimate (excluding contingencies):

   i. 7.00% of the first $50,000.00
   ii. Plus 3.85% for the next $250,000.00 ($50,001.00 thru $300,000.00)
   iii. Plus 1.95% over $300,000.00

3. 5 complete sets of improvement plans (blue-line or black-line copies)

4. 5 sets of specifications (use San Joaquin County Standard Specifications and Special Provisions as a guide)

5. 1 complete set of preliminary soils report including R-values and structural section calculations

6. Storm drain calculations (Hydrology, sub-area map, pipeline, hydraulic design, retention/detention basin, pump system, etc., as applicable)

7. Water and sanitary sewer design data and calculations, if applicable

8. 1 draft final map, if applicable

B. Field inspection fee based on approved Engineer's Estimate (excluding contingencies) must be submitted prior to or at time of submittal of original mylars:

1. 5.50% for the first $200,000.00
2. Plus 3.85% for the next $300,000.00 ($200,001.00 thru $500,000.00)
3. Plus 2.75% for the next $500,000.00 ($500,001.00 thru $1,000,000.00)
4. Plus 2.25% over $1,000,000.00

Public Works
San Joaquin County
Working for YOU

Proposed Hospital Improvements for Mathews & Manthey Rds.

Plan Check Fees

$(7\%)(\$50,000) = \$3,500$

$(3.85\%)(\$76,141.75) = \$2,931$

$\$6,431$

Field Inspection Fees

$(5.5\%)(\$126,141.75) = \$6,938$

Total Fees Due

$\$6,431$

$+ \$6,938$

$\$13,369$

SAN JOAQUIN COUNTY VA/HOSPITAL DIALYSIS CLINIC SITE PACKAGE					
STREET IMPROVEMENTS					
Opinion of Probable Construction Cost					
Item	**Description**	**Unit**	**Estimated Quantity**	**Unit Cost**	**Estimated Cost**
1	Dust Control	LS	1	$1,500.00	$1,500.00
2	Traffic Control	LS	1	$8,000.00	$8,000.00
3	Sawcut and Remove Asphalt	SQFT	3,415	$1.25	$4,268.75
4	Clearing and Grubbing	LS	1	$3,500.00	$3,500.00
5	Rough Grading	CY	1,500	$0.22	$330.00
6	3" AC Over 6.5" AB	SQFT	22,036	$1.75	$38,563.00
7	Curb & Gutter	LF	1,450	$12.00	$17,400.00
8	Sidewalk	SQFT	4,780	$3.50	$16,730.00
9	Handicap Ramps	EA	5	$2,500.00	$12,500.00
10	Storm Drain Pipe 12-Inch	LF	60	$15.00	$900.00
11	Storm Drain Inlet	EA	6	$1,200.00	$7,200.00
12	Commercial Driveway 25-feet	EA	1	$3,500.00	$3,500.00
13	Remove and Relocate Sign	EA	5	$750.00	$3,750.00
14	Striping & Signage	LS	1	$8,000.00	$8,000.00
		TOTAL			$126,141.75