TAFT PARK

TAFT ELEMENTARY SCHOOL

VERIZON CELL SITE

CITY OF STOCKTON
SAN JOAQUIN COUNTY

DOWNING AVE

8"PVC

S TURNPIKE RD

BORE RECEIVE PIT

12"DI

94'

86'

VAULT B9

PROPOSED CONSTRUCTION

PLACE 30"x48" HANDHOLE 6' BACK OF CURB. SEE ENCLOSURE DETAIL ON SHEET 2.

BORE ORIGINATION PIT

8"PVC

72"SS

8"SS

PROPOSED CONSTRUCTION - 762'

DIRECTIONAL DRILL AND PLACE (3) 1-1/4" HDPE DUCTS. MAINTAIN MIN. 48" DEPTH OF COVER.

24'

40'

22'

B

CONTINUES ON SHEET 5

B

S TURNPIKE RD

PROPOSED CONSTRUCTION - 41'

DIRECTIONAL DRILL AND PLACE (3) 1-1/4" HDPE DUCTS. MAINTAIN MIN. 48" DEPTH OF COVER.

SCALE: 1"=40'

0 20' 40'

DIGALERT

Call: TOLL FREE
1-800-227-2600

AT LEAST TWO DAYS BEFORE YOU DIG

UNDERGROUND SERVICE ALERT NORTH

verizon

Level(3) COMMUNICATIONS

DATALOG

INSTALLATION OF FIBER OPTIC FACILITIES

MCKINLEY AVENUE DESIGN

SHEET: 6 OF: 21

Hector A. Lara

DESIGN ENGINEER

DATE: 11/15/06

RCE NO: 49312

EXP DATE: 9/30/08