F:\04cod\04233\CIVIL\STRIPING PLANS\04233-C-1-DEMO.dwg -- 06/04/07

EP-07-172-1

CA: 800-642-2444
NV: 800-227-2600
CALL BEFORE YOU DIG
UNDERGROUND SERVICE ALERT

HORIZONTAL BENCHMARK:

CALIFORNIA STATE HIGHWAY DIVISION BRASS CAP #23,
LOCATED ON THE TRAFFIC ISLAND, APPROXIMATE
CENTERLINE OF ROTH ROAD, WEST OF HARLAN ROAD.

PAVEMENT TO BE DEMOLISHED AND REMOVED FROM SITE BY CONTRACTOR

CONTRACTOR SHALL REMOVE EXISTING LANE STRIPING FROM ROTH ROAD

PROPOSED SAWCUT LINE SHOWED AS CONCEPTUAL ONLY SHALL BE VERIFIED AND DETERMINED BY PUBLIC WORKS INSPECTOR ALL PAVEMENT DEEMED IN POOR CONDITION SHALL BE REMOVED FROM SITE BY CONTRACTOR

CONTRACTOR SHALL REMOVE EXISTING CENTERLINE STRIPING FROM HARLAN ROAD

CONTRACTOR SHALL DEMOLISH, REMOVE, AND HAUL AWAY EXISTING MEDIAN CURBING FROM SITE

CONTRACTOR SHALL RELOCATE SIGN INSIDE REDESIGNED MEDIAN AFTER COSTRUCTION

CONTRACTOR SHALL REMOVE EXISTING STOP BAR AND PAVEMENT MARKINGS FROM SITE

CONTRACTOR SHALL REMOVE 11' OF EXISTING CENTERLINE STRIPING FROM HARLAN ROAD

HARLAN ROAD

ROTH ROAD

SHEET: OF: 1 3	OFFSITE LANE WIDENING AUTO/TRUCK FUEL CENTER DEMOLITION PLAN LATHROP SAN JOAQUIN CALIFORNIA	SIEGFRIED ENGINEERING, INC. • Civil Engineering • Land Surveying • Structural Engineering • Planning 4045 Coronado Avenue • Stockton, CA 95204 209 943-2021 • Fax: 209 942-0214 E-Mail: mail@siegfriedeng.com

Plan File No.

Comp. File No.

REGISTERED PROFESSIONAL ENGINEER
LEX A. CORRALES
No. 21447
Expires 9-30-07
CIVIL
STATE OF CALIFORNIA

DATE SIGNED: 6-4-07

DATE:	6/1/07
SCALE:	1"=20'
DRAWN BY:	DAM
PROJ. ENGR:	DAM
PROJ. MGR:	LAC
FB:	NO:

REVISIONS			
No.	Descriptions	Date	App.