: COUNTY PORTION

All others 4"Φ

TABLE 2				
BORING LOCATIONS AND DEPTHS – PIPELINES				
Boring No.	Approximate Station	Approximate Offset (ft)	Approximate Boring Depth (ft)	Remarks
1	1+00		30	8"Φ
2	12+50		20	
3	25+00		20	
4	37+50		20	
5	50+00		20	Piezometer
6	62+50		35	Trenchless Crossing 8"Φ
7	65+00		35	Trenchless Crossing 8"Φ
8	77+50		20	
9	90+00		20	Piezometer
10	102+50		20	
11	115+00		20	
12	127+50		20	
13	140+00		20	
14	152+50		20	Piezometer
15	165+00		20	
16	178+50		55	Trenchless Crossing, CPT 8"Φ
17	183+50		35	Trenchless Crossing, CPT 8"Φ
18	197+50		20	Piezometer
19	222+50		20	
20	247+50		20	Piezometer
21	272+50		20	
22	285+00		20	Piezometer
23	300+50		40	Trenchless Crossing, CPT 8"Φ
24	304+50		40	Trenchless Crossing, CPT 8"Φ
25	319+50		20	Piezometer
26	332+00		20	
27	357+50		20	
28	375+00		20	Piezometer
29	394+50		20	
30	413+00		20	
31	432+00		35	Trenchless Crossing 8"Φ
32	439+50		35	Trenchless Crossing 8"Φ
33	464+00		20	
34	490+00		20	
35	515+00		20	
36	539+00		20	
37	558+00		20	

All others 4"ϕ

Boring No.	Approximate Station	Approximate Offset (ft)	Approximate Boring Depth (ft)	Remarks	
38	569+00		35	Trenchless Crossing	8"ϕ
39	576+00		35	Trenchless Crossing	8"ϕ
40	595+00		20		
41	614+00		20		
42	626+50		20		
43	639+00		20		
44	651+50		20		
45			18		
46			18		
47			35	Trenchless Crossing	8"ϕ
48			35	Trenchless crossing	8"ϕ
49			18		
50			35	Trenchless crossing	8"ϕ
51			35	Trenchless crossing	8"ϕ
52			18		

** Borings 45 through 52 have been allocated for the treated water line