## PAVEMENT DELINEATION QUANTITIES

| SHEET No. | LOCATION | DETAIL No. | PAVEMENT MARKER | | | THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE) | 4" THERMOPLASTIC TRAFFIC STRIPE | | | 8" THERMOPLASTIC TRAFFIC STRIPE | REMOVE TRAFFIC STRIPE | REMOVE PAVEMENT MARKING | RMOVE PAVEMENT MARKER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | (NON-RELECTIVE) | (RETROREFLECTIVE) | | | | | | | | | |
| | | | TYPE "A" (EA) | TYPE 'G' (EA) | TYPE 'D' (EA) | 12" SOLID WHITE (FT) | SOLID YELLOW (FT) | BROKEN WHITE (FT) | SOLID WHITE (FT) | SOLID WHITE (FT) | (FT) | (SQFT) | (EA) |
| S01 | "MA" LINE | 27B | | | | | | | 3942 | | | | |
| | "MA" LINE | 22 | | | 108 | | 2550 | | | | | | |
| | "MA" LINE | 38 | | 11 | | | | | | 257 | | | |
| | "MA" LINE | 29 | | | 47 | | 2218 | | | | | | |
| S02 | "MA" LINE | | | | | | | | | | | | |
| | "MA" LINE | 27B | | | | | | | 4152 | | | | |
| | "MA" LINE | 22 | | | 62 | | 1476 | | | | | | |
| | "MA" LINE | | | | | | | | 412 | | | | |
| | "MA" LINE | 38 | | 43 | | | | | | 1015 | | | |
| | "MA" LINE | 29 | | | 112 | | 5342 | | | | | | |
| | "Y" LINE | 22 | | | 30 | | 712 | | | | | | |
| | "Y" LINE | | | | | 40 | | | | | | | |
| S03 | "FC" LINE | 27B | | | | | | | 3588 | | 960 | | |
| | "FC" LINE | 38 | | 32 | | | | | | 770 | | | |
| | "FC" LINE | 29 | | | 103 | | 4934 | | | | | | |
| | "FC" LINE | 22 | | | 24 | | 548 | | | | 960 | | 42 |
| | "FC" LINE | 9 | | 24 | | | | 1105 | | | | | |
| | "FC" LINE | | | | | | | | 200 | | | | |
| | "FC" LINE | | | | | 136 | | | | | | | |
| | "MA" LINE | 27B | | | | | | | 181 | | | | |
| | "MA" LINE | 29 | | | 4 | | 110 | | | | | | |
| | "MA" LINE | 38 | | 5 | | | | | | 100 | | | |
| | "MA LINE | | | | | | | | 50 | | | | |
| | "MA" LINE | | | | | 39 | | | | | | | |
| S04 | "MA_C" LINE | 22 | | | 14 | | 300 | | | | 42 | | 6 |
| | "MA_C" LINE | 27B | | | | | | | 357 | | 20 | | |
| | "MA_C" LINE | | 18 | | | 14 | | | | | | 32 | |
| TOTAL | | | 18 | 115 | 504 | 229 | 18190 | 1105 | 12882 | 2142 | 1982 | 32 | 48 |

## SIGN QUANTITIES

| SHEET No. | SIGN NO. | CODE | PANEL SIZE (IN) | ROADSIDE SIGN | |
|---|---|---|---|---|---|
| | | | | WOOD POST | STEEL POST |
| S01 | 1-1 | W13-1(30) | 24x24 | | 1 |
| | 1-1 | W16-9p | 24x12 | | |
| | 1-2 | W1-2a(Lt)(30) | 30x30 | | 1 |
| | 1-3 | W2-2(Rt) | 30x30 | | 1 |
| | 1-4 | R3-7 | 30x30 | | 1 |
| | 1-5 | R1-1 | 30x30 | | 1 |
| | 1-6 | W1-7 | 48x24 | | 1 |
| | 1-7 | W1-2a(Rt)(30) | 30x30 | | 1 |
| | 1-8 | W2-2(Lt) | 30x30 | | 1 |
| | 1-9 | W1-2a(Rt)(30) | 30x30 | | 1 |
| S02 | 2-1 | R61-19 | 30x24 | | 1 |
| | 2-2 | W3-1 | 36x36 | | 1 |
| | 2-3 | R1-1 | 30x30 | | 1 |
| | 2-4 | W1-2a(Lt)(30) | 30x30 | | 1 |
| | 2-5 | W3-1 | 36x36 | | 1 |
| | 2-6 | R1-1 | 30x30 | | 1 |
| | 2-7 | W3-3 | 36x36 | | 1 |
| | 2-8 | W13-1(30) | 24x24 | | 1 |
| S03 | 3-1 | W13-1(30) | 24x24 | 1 | |
| | 3-1 | W16-8p | 30x18 | | |
| | 3-2 | W1-4(Rt) | 36x36 | 1 | |
| | 3-3 | W3-3 | 36x36 | 1 | |
| | 3-4 | R30E(CA) | 18x24 | 1 | |
| | 3-5 | R30E(CA) | 18x24 | 1 | |
| | 3-6 | R3-7 | 30x30 | 1 | |
| | 3-7 | R30E(CA) | 18x24 | 1 | |
| | 3-8 | W1-7 | 48x24 | 1 | |
| | 3-8 | TYPE N(CA) | 24x24 | | |
| | 3-9 | R30E(CA) | 18x24 | 1 | |
| | 3-10 | R30E(CA) | 18x24 | 1 | |
| | 3-11 | R30E(CA) | 18x24 | 1 | |
| S04 | 4-1 | W3-1 | 36x36 | | 1 |
| TOTAL | | | | 11 | 18 |

## PAVEMENT MARKING QUANTITIES

| THERMOPLASTIC PAVEMENT MARKING | QUANTITY (EA) | AREA (SQFT) |
|---|---|---|
| "STOP" | 6 | 132 |
| "SIGNAL" | 2 | 64 |
| "AHEAD" | 6 | 186 |
| TYPE IV (L) ARROW | 9 | 135 |
| TYPE IV (R) ARROW | 6 | 90 |
| TOTAL | | 607 |

## REMOVE ROADSIDE SIGN

| SHEET NUMBER | QUANTITY (EA) |
|---|---|
| S03 | 3 |
| TOTAL | 3 |

## OBJECT MARKER QUANTITIES

| SHEET No. | LOCATION | CODE | QUANTITY (EA) |
|---|---|---|---|
| S03 | "MA" LINE | K-2(CA) | 1 |
| | "FC" LINE | K-2(CA) | 1 |
| TOTAL | | | 2 |

## CHANNELIZERS (SURFACE MOUNTED) (LEFT IN PLACE)

| SHEET NUMBER | QUANTITY (EA) |
|---|---|
| S02 | 17 |
| S03 | 21 |
| TOTAL | 38 |

## DELINEATOR QUANTITIES

| SHEET No. | RETROREFLECTIVE DELINEATOR |
|---|---|
| | TYPE F |
| S01 | 24 |
| S02 | 29 |
| TOTAL | 53 |

CALL BEFORE YOU DIG UNDERGROUND SERVICE ALERT USA 800-227-2600

REGISTERED PROFESSIONAL ENGINEER — KELLY BURKE No. C68431 — CIVIL — STATE OF CALIFORNIA

| Revision No. | Description | Date | By | Apprvd. By |
|---|---|---|---|---|
| – | – | – | – | – |

HDR Engineering, Inc.

**MANTHEY ROAD RELOCATION**

**SIGNING AND STRIPING QUANTITIES**

DEPARTMENT OF PUBLIC WORKS
CITY OF STOCKTON, CALIFORNIA

| | | | |
|---|---|---|---|
| SCALE | | APPROVED BY: AR 8-31-11 DATE | SHEET NO. S05 |
| DESIGNED BY | KB/TK | | 26 OF 46 |
| DRAWN BY | KB | | |
| CHECKED BY | T.KHOU | CITY ENGINEER STOCKTON, CALIFORNIA | 99-01 PROJECT NO. |
| RECORD DWGS. | – | | |

5149.25C

PS-12-00393(20)

C:_PROJECTS\Manthey road\320 1 0063039207-505\Former 506\dwg, 8/30/2011 4:13:56 PM