SEWER CONNECTION PLAN

SCALE: 1"=20'

PS-1201217 3/3

CONTRACTOR ALERT!!!!!
ALL EXISTING UTILITY ELEVATIONS MUST BE VERIFIED VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTING ANY PROPOSED UTILITIES

BAR SCALE
20 0 20 40
(IN FEET)
1 inch = 20 feet

CONSTRUCTION NOTES:

1. CONSTRUCT NEW 6" SEWER STUB OFF OF 12" MAIN & PLACE 52 LF OF 6" SEWER LINE AT S=0.020; FL@12" MAIN= 18.30, FL@STUB END=19.34.
2. CONSTRUCT CLEANOUT TO GRADE AT THE STUB END SET 1 FOOT BEHIND THE BACK OF SIDEWALK; FL=19.34
3. PLACE 60 L.F. OF 6" SEWER PIPE @ S=0.020 FROM CLEANOUT#2 TO CLEANOUT #4 SET 5 FT. OUTSIDE THE EXISTING BUILDING; FL@CO#2= 19.34, FL@CO#4= 20.54.
4. CONSTRUCT CLEANOUT TO GRADE 5 FT. OUTSIDE THE EXISTING BUILDING; FL=20.54.
5. PLACE 3 L.F. OF 6" SEWER PIPE @ S=0.020 FROM CLEANOUT#4 TO THE EXISTING BUILDING.
6. POTHOLE EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY THERE ARE NO CONFLICTS WITH THE NEW PROPOSED SEWER LINE. ANY CONFLICTS FOUND SHALL BE REPORTED TO THE ENGINEER SO THAT DESIGN CHANGES CAN BE MADE PRIOR TO CONSTRUCTION BEGINNING.

REGISTERED PROFESSIONAL ENGINEER
ROSS E. PEABODY
No. C51090
Exp. 9-30-11
CIVIL
STATE OF CALIFORNIA

Peabody Engineering
1700 Alhambra Blvd., Suite 102
Sacramento, CA. 95816
(916) 731-8088 office (916) 731-8089 fax

No.	Description	Engr Init.	CITY APPROVAL By	Date

4232 E. MAIN STREET SEWER CONNECTION PLAN

DOLLAR GENERAL

SEWER CONNECTION PLAN

DRAWN BY: JAV
DESIGNED BY: JAV
CHECKED BY: JAV
HORIZONTAL: 1"=20'
VERTICAL: NONE
DATE: 1/27/2012
SHEET NO. C3 OF C3
JOB NO.:0800.004

G:\0410.001 - Dollar General\Sheet03.dwg 1/31/12 9:28am Ross