



- GENERAL NOTES:**
- Elevations are based on S.T. County Datum. County Bench S.S. in Light Pole S.W. Corner Cherokee Lane & Wilmarth Rd.
 - The site is presently in walnut orchard. Owner will clear & grub tree, disposing same off-site.
 - For Construction Requirements see Standards entitled "Specifications for construction of Greg Lewis Development"
 - Existing ground is flat. There is no established drainage pattern. Surface water from pavement will drain to adjacent land. Drainage from individual lots will be retained on the property.
 - Water and Sanitary facilities are to be provided on individual lots by owners.
 - Encroachment Permits will be required before drive ways are constructed.

STRUCTURAL DESIGN				
T.I.	R'VALUE	G.E. Req.	STRUCTURE	G.E.
4.0	5	1.22'	0.17' AC.	0.43'
			0.75' AB.	0.83'
			TOTAL	1.26'

CONSTRUCTION QUANTITIES		
Asphalt Concrete Type 'B'	205	tons
Aggregate Base 'C1'2'	855	tons
Roadway Excavation	200	cu. yds
Street Sign	1	only
Monument	1	only
12" C.M.R.	44	lin. feet
Barricade	1	only

APPROVED BY:

John Thomas
SAN JOAQUIN COUNTY FIRE WARDEN

L. O. HUNTER, CIVIL ENGINEER & SURVEYOR
R. C. E. # 24305

GREG LEWIS DEVELOPMENT
PROPOSED ROAD PLAN, SECTION & PROFILE

COUNTY OF SAN JOAQUIN, DEPT. OF PUBLIC WORKS
Approved: *William J. Davis* Date: 2-8-77
Director of Public Works

REVISIONS No.	DATE	BY	DESIGN	SCALE
			Design: R.V.G.	As Shown.
			Approved: <i>William J. Davis</i>	
			P.C.E. No. 10,048	