



COUNTY OF SAN JOAQUIN

DEPARTMENT OF PUBLIC WORKS

P.O. BOX 1810-1810 E. HAZELTON AVENUE
STOCKTON, CALIFORNIA 95201
(209) 468-3000
FAX # (209) 468-9324

Permit No: PS-1902461
Date Issued: 07/25/2019
Start Date: 07/29/2019
Exp. Date: 07/31/2019
Project No: PWP7110005
Quad: SE

ENCROACHMENT PERMIT

To: BNSF/ALERT-O-LITE
2020 N. WINERY
FRESNO, CA 93703

Encroachment Type:

Temp. Road Closure			
--------------------	--	--	--

Location:

LONE TREE RD. AND SEXTON RD. AT BNSF CROSSINGS

In compliance with your request of **07/25/2019**, permission is hereby granted to do work in County right-of-way as shown on attached application and subject to all the terms, conditions and restrictions written below or printed as general or special provisions on any part of this form. See reverse side and attached sheet, if any.

Trench excavations for service connections will not be permitted within ten feet (10') of pavement centerline unless otherwise approved by the Director. Surface of trench patches shall match in kind and be smooth and even with that of abutting surface. Special attention shall be given to depth of utilities through roadside area in anticipation of future drainage facilities, road profile and/or frontage development. All underground utility facilities are to be established and accurately dimensioned on sketches from surveyed centerline of road right of way, or from right of way (border) lines.

Permittee shall call the Department of Public Works, Field Engineering Division (Permit Inspections) at (209)953-7421 at least forty-eight hours prior to beginning any work within the County right of way. All work performed under this permit shall conform to the rules and regulations pertaining to safety established by the California Division of Industrial Safety and Cal-OSHA.

The jobsite shall be kept in a safe condition at all times by the daily removal of any excess dirt or debris which might be a hazard to either pedestrian or automobile traffic. All necessary traffic convenience and warning devices and personnel shall be provided, placed and maintained by and at the sole expense of the Permittee in accordance with the latest edition of the CALTRANS Manual of Traffic Control.

After completion of the work permitted herein, all debris, lumber, barricades, or any excess material shall be removed and the jobsite left in a neat workmanlike manner. Immediately following completion of construction permitted herein, Permittee shall fill out and mail notice of completion (see attached post card) provided by Grantor.

Special Comments:

Traffic Control Per MUTCD*****BNSF to close Sexton Rd. and Lone Tree Rd. @ crossings from 9:00 AM on 7/29/2019 to 5:00 PM on 7/31/2019 for RR Crossing repairs*****

FORMS:

SS/WW, Special	Conditions	
----------------	------------	--

Est. Permit Fee: \$0.00

WHITE -Permittee
GOLDENROD -PWD Central File
YELLOW -Field Inspection
PINK -Permit Section

KRIS BALAJI, Director
Department of Public Works

By: Auni Taha
Permit Section

ENCROACHMENT PERMIT GENERAL PROVISIONS

13-1

1. This permit is issued under and subject to all laws and ordinances of agencies governing the encroachment herein permitted. See the following references:

STREETS AND HIGHWAYS CODE

1. Division 1, Chapter 3
2. Division 2, Chapter 2, Section 942
3. Division 2, Chapter 4, Section 1126
4. Division 2, Chapter 5.5 and Chapter 6

SAN JOAQUIN COUNTY ORDINANCES NUMBERED: 324, 441, 648, 662, 672, 695, 700, 860, 892, 3359, and 3675.

2. It is understood and agreed by the Permittee that the performance of any work under this permit shall constitute an acceptance of all the provisions contained herein and failure on the Permittee's part to comply with any provision will be cause for revocation of this permit. Except as otherwise provided for public agencies and franchise holders, this permit is revocable on five days notice.
3. All work shall be done subject to the supervision of and the satisfaction of the grantor. The Permittee shall at all times during the progress of the work keep the County Highway in as neat and clean condition as is possible and upon completion of the work authorized herein, shall leave the County Highway in a thoroughly neat, clean and usable condition.
4. The Permittee also agrees by the acceptance of this permit to properly maintain any encroachment structure placed by the Permittee on any part of the County Highway and to immediately repair any damage to any portion of the highway, which occurs as a result of the maintenance of the said encroachment structure, until such time as the Permittee may be relieved of the responsibility for such maintenance by the County of San Joaquin.
5. The Permittee also agrees by the acceptance of this permit to make, at its own expense, such repairs as may be deemed necessary by the County Department of Public Works.
6. It is further agreed by the Permittee that whenever construction, reconstruction or maintenance work upon the highway is necessary, the installation provided for herein shall, upon request of the County Department of Public Works, be immediately moved or removed by and at the sole expense of the Permittee.
7. No material used for fill or backfill in the construction of the encroachment shall be borrowed or taken from within the County right of way.
8. All work shall be planned and carried out with as little inconvenience as possible to the traveling public. No material shall be stacked within eight feet (8') of the edge of the pavement or traveled way unless otherwise provided herein. Adequate provision shall be made for the protection of the traveling public. Traffic control standards shall be utilized including barricades; approved signs and lights; and flagmen, as required by the particular work in progress.
9. The Permittee, by the acceptance of this permit, shall assume full responsibility for all liability for personal injury or damage to property which may arise out of the work herein permitted or which may arise out of the failure of the part of the Permittee to properly perform the work provided under this permit. In the event any claim of such liability is made against the County of San Joaquin or any department, official or employee thereof, the Permittee shall defend, indemnify, and hold each of them harmless for such claim.
10. All backfill material is to be moistened as necessary and thoroughly compacted with mechanical means. If required by the County Director of Public Works, such backfill shall consist of gravel or crushed rock. The Permittee shall maintain the surface over structures placed hereunder as may be necessary to insure the return of the roadway to a completely stable condition and until relieved of such responsibility by the County Department of Public Works. Wherever a gravel, crushed rock or asphalt surface is removed or damaged in the course of work related to the permitted encroachment, such material shall either be separately stored and replaced in the roadway as nearly as possible in its original state or shall be replaced in kind, and the roadway shall be left in at least as good a condition as it was before the commencement of operations of placing the encroachment structure.
11. Whenever it becomes necessary to secure permission from abutting property owners for the proposed work, such authority must be secured by the Permittee prior to starting work.
12. The current and future safety and convenience of the traveling public shall be given every consideration in the location and methods of construction utilized.
13. The Permittee is responsible for the preservation of survey monuments located within the area of work herein permitted. Prior to the start of construction, survey monuments that potentially may be disturbed shall be located and referenced by a Licensed Land Surveyor, and a Corner Record filed with the County Surveyor. Any Survey Monuments disturbed during the course of construction shall be reestablished by a Licensed Land Surveyor and another Corner Record filed with the County Surveyor. (Land Surveyors' Act Section 8771)
14. Prior to any excavation, the Permittee shall notify USA North (Underground Service Alert of Northern California and Nevada) at 811 or 800-227-2600 forty-eight (48) hours in advance.

SPECIAL CONDITIONS FOR BNSF
RAILROAD TRACK CROSSING REPAIRS
ENCROACHMENT PERMIT

1. Maintain traffic controls for all roads. Traffic control delays shall not exceed 10 minutes. Two-way traffic shall be maintained during non-working hours with excavated areas backfilled or plated. During working hours, two-way traffic control shall be maintained with one lane open and appropriate flaggers.
2. Traffic Control Signs shall be removed or sacked when roadway is reopened on 7/31/2019.
3. Access to all properties within the work areas shall be maintained at all times.
4. Residents and businesses shall be notified in writing, as approved by the County, 48 hours in advance of any impacts to their access.
5. Any areas where parking is to be restricted shall have signs noting the restrictions in place at least 48 hours in advance.
6. All pavement conforms shall be ground to provide a flush surface. Shoulder areas shall be brought up to the finish grade as directed by the County.
7. All destroyed or obliterated pavement markings must be replaced in kind by the permittee. Typical pavement markings include but not limited to lane lines, centerlines, stop and stop ahead legends, limit lines, raised pavement markers and miscellaneous delineators.
8. The Permittee is responsible for the preservation of survey monuments located within the area of work herein permitted. Prior to the start of construction, survey monuments that potentially may be disturbed shall be located and referenced by a Licensed Land Surveyor, and a Corner Record filed with the County Surveyor. Any Survey Monuments disturbed during the course of construction shall be reestablished by a Licensed Land Surveyor and another Corner Record filed with the County Surveyor. (Land Surveyors' Act Section 8771)
9. Class II Aggregate Base shoulder backing is required from the edge of pavement, a minimum of 4-inches thick by 4-feet wide.
10. Contractor shall establish existing roadway and drainage grades within the construction area. Any repair to roadways and adjacent areas shall match existing grades. Any proposed grade changes shall receive prior approval from County.
11. County roads shall be kept clean from mud and debris at all times along the access points and work zone areas during entire project. All standard roadway striping and signage shall be clearly visible, maintained and restored throughout the construction zone during and after the project.
12. The contractor shall not conduct construction operations in rain or heavy fog conditions.

APPLICATION FOR ENCROACHMENT PERMIT

PLEASE PRINT:

Date 7-15-19

To: San Joaquin County
Department of Public Works

BNSF / ALERT-O-LITE
(Applicant Name)

2436 FOUNDRY PARK AVE
(Mailing Address)

FRESNO CA 93708-4531
(City, State, Zip Code)

BAAD 559-801-5668
(Area Code - Telephone Number)

BAADH@ALERTOLITE.COM
(Email Address)

OFFICE USE ONLY

JOB # 110005 REF # _____
APN _____ CR # _____
EXP. DATE 7/31/19
VALID 7/25/19 TO 7/31/19 DRIVEWAYS: _____
STREET SEXTON RD. & LONE TREE RD. * _____
AREA ESCALON QUAD SE * _____
TYPE TEMP ROAD CLOSURE * _____
FORMS SS/WW
NOTES _____

ROAD CLOSURE OF SEXTON RD. &
LONE TREE RD. @ BNSF RR CROSSINGS.
FROM MONDAY (7/29) THRU WEDNESDAY
(7/31) * BOTH CROSSING CLOSED AT THE
SAME TIME.

Sketch (Detailed plans may be submitted)

BNSF TO TEAR OUT AND REPLACE
2 - CROSSINGS
STEEL GANE IS COMING THRU THE AREA
LONE TREE W/O SEXTON
SEXTON S/O LONE TREE (BOTH CLOSED AT THE SAME TIME)

The undersigned hereby applies for permission to excavate, construct and/or otherwise encroach on County Highway Right-of-Way on the _____ side of _____ approximately _____ feet/mile _____ of _____, by performing the following work (description of work):

STEEL GANE WILL START BEFORE THE
BEGINNING OF AUGUST
WILL CONFIRM DATES WHEN I GET THEM

Work will commence on or after _____ for approximately 13 days.

I, the undersigned, certify that I am the owner of the respective property, or am qualified to represent the owner and agree to do the work described above in accordance with the rules and regulations of San Joaquin County and subject to inspection and approval.

[Signature]
Signature of Applicant - Title

ALERT-O-LITE
BAAD

7-15-19
Date

Steel Gant (BNSF) Lone Tree & Sexton Crossing San Joaquin County

Legend

- = Detour Route
 = Road Closure

Manifest

43 x Barricade
2 x CMS : Changeable message Board
5 x M4-10L: Detour Left
6 x M4-10R: Detour Right
4 x PN: Pre-Notification
4 x R11-2: Road Closed
6 x R11-4: Road Closed To Thru Traffic
5 x Typelll
3 x W20-1(1500) : Road Work (1500 ft)
6 x W20-1: Road Work Ahead
2 x W20-2(500): Detour Ahead (500)
7 x W20-3(1000): Road Closed (1000 ft)
3 x W20-3(1500): Road Closed (1500 ft)
5 x W20-3(500): Road Closed (500 ft)
5 x W20-3: Road Closed Ahead

Notes:

1. All W20 signs will be spaced 500 ft from the next sign ahead. Except for those installed on barricades, all M4-10 signs to be located 500 ft in advance of intersection.
2. Sc3 signs are to be located on the detour route at intervals not exceeding 1/4 mile.
3. "Road Closure, Road Closed to Thru Traffic" will all be setup on type III's barricade

Permit:

Date: 00/00/2019 Drawn By: Christine Yu AOL Job #: 013866
 Drawn For: Steel Gant Closure Project: Lone Tree & Sexton Crossing

Comments:

Start: 7/29 - 7/31/2019, 9am - 24hours
 Duration: 3 days
 Job Site Contact: Brad Hunsaker (559) 801-5668

TCP Checked By: Brad Hunsaker
 Prepared By: Alert-O-Lite, Inc.
 Ph: (559) 265-4550 Fax (559) 265-4549

Alert-O-Lite
 9500
 1000

- Notes:
1. Alert-O-Lite to Setup
 2. Contractor to Maintain
 3. All Traffic Control will meet CA MUTCD Standards

(PN) = 48" Pre-Notification Signs

THIS CROSSING
WILL BE
CLOSED
7-29-19
THRU
7-31-19

Pre Notification Placed
7/25/2019



