



COUNTY OF SAN JOAQUIN

DEPARTMENT OF PUBLIC WORKS
P.O. BOX 1810-1810 E. HAZELTON AVENUE
STOCKTON, CALIFORNIA 95201
(209) 468-3000
FAX # (209) 468-9324

Permit No: PS-1902674
Date Issued: 08/13/2019
Start Date: 08/15/2019
Exp. Date: 10/01/2019
Project No: PWP730079
Quad:

UE/CR/PM NO:A01ME0L

ENCROACHMENT PERMIT

To: AT & T - FRESNO
5555 E. OLIVE RM#300III
FRESNO, CA 93727

Encroachment Type:

Trench			
--------	--	--	--

Location:

E/S HARLAN RD 420' N/O ROTH RD

In compliance with your request of 08/13/2019, permission is hereby granted to do work in County right-of-way as shown on attached application and subject to all the terms, conditions and restrictions written below or printed as general or special provisions on any part of this form. See reverse side and attached sheet, if any.

Trench excavations for service connections will not be permitted within ten feet (10') of pavement centerline unless otherwise approved by the Director. Surface of trench patches shall match in kind and be smooth and even with that of abutting surface. Special attention shall be given to depth of utilities through roadside area in anticipation of future drainage facilities, road profile and/or frontage development. All underground utility facilities are to be established and accurately dimensioned on sketches from surveyed centerline of road right of way, or from right of way (border) lines.

Permittee shall call the Department of Public Works, Field Engineering Division (Permit Inspections) at (209)953-7421 at least forty-eight hours prior to beginning any work within the County right of way. All work performed under this permit shall conform to the rules and regulations pertaining to safety established by the California Division of Industrial Safety and Cal-OSHA.

The jobsite shall be kept in a safe condition at all times by the daily removal of any excess dirt or debris which might be a hazard to either pedestrian or automobile traffic. All necessary traffic convenience and warning devices and personnel shall be provided, placed and maintained by and at the sole expense of the Permittee in accordance with the latest edition of the CALTRANS Manual of Traffic Control.

After completion of the work permitted herein, all debris, lumber, barricades, or any excess material shall be removed and the jobsite left in a neat workmanlike manner. Immediately following completion of construction permitted herein, Permittee shall fill out and mail notice of completion (see attached post card) provided by Grantor.

Special Comments:

Traffic Control Per MUTCD

FORMS:

SS/WW, R-29		
-------------	--	--

Est. Permit Fee: \$620.90

WHITE	-Permittee
GOLDENROD	-PWD Central File
YELLOW	-Field Inspection
PINK	-Permit Section

KRIS BALAJI, Director
Department of Public Works

By: _____

Permit Section

ENCROACHMENT PERMIT GENERAL PROVISIONS

13-1

1. This permit is issued under and subject to all laws and ordinances of agencies governing the encroachment herein permitted. See the following references:
STREETS AND HIGHWAYS CODE
 1. Division 1, Chapter 3
 2. Division 2, Chapter 2, Section 942
 3. Division 2, Chapter 4, Section 1126
 4. Division 2, Chapter 5.5 and Chapter 6

SAN JOAQUIN COUNTY ORDINANCES NUMBERED: 324, 441, 648, 662, 672, 695, 700, 860, 892, 3359, and 3675.

2. It is understood and agreed by the Permittee that the performance of any work under this permit shall constitute an acceptance of all the provisions contained herein and failure on the Permittee's part to comply with any provision will be cause for revocation of this permit. Except as otherwise provided for public agencies and franchise holders, this permit is revocable on five days notice.
3. All work shall be done subject to the supervision of and the satisfaction of the grantor. The Permittee shall at all times during the progress of the work keep the County Highway in as neat and clean condition as is possible and upon completion of the work authorized herein, shall leave the County Highway in a thoroughly neat, clean and usable condition.
4. The Permittee also agrees by the acceptance of this permit to properly maintain any encroachment structure placed by the Permittee on any part of the County Highway and to immediately repair any damage to any portion of the highway, which occurs as a result of the maintenance of the said encroachment structure, until such time as the Permittee may be relieved of the responsibility for such maintenance by the County of San Joaquin.
5. The Permittee also agrees by the acceptance of this permit to make, at its own expense, such repairs as may be deemed necessary by the County Department of Public Works.
6. It is further agreed by the Permittee that whenever construction, reconstruction or maintenance work upon the highway is necessary, the installation provided for herein shall, upon request of the County Department of Public Works, be immediately moved or removed by and at the sole expense of the Permittee.
7. No material used for fill or backfill in the construction of the encroachment shall be borrowed or taken from within the County right of way.
8. All work shall be planned and carried out with as little inconvenience as possible to the traveling public. No material shall be stacked within eight feet (8') of the edge of the pavement or traveled way unless otherwise provided herein. Adequate provision shall be made for the protection of the traveling public. Traffic control standards shall be utilized including barricades; approved signs and lights; and flagmen, as required by the particular work in progress.
9. The Permittee, by the acceptance of this permit, shall assume full responsibility for all liability for personal injury or damage to property which may arise out of the work herein permitted or which may arise out of the failure of the part of the Permittee to properly perform the work provided under this permit. In the event any claim of such liability is made against the County of San Joaquin or any department, official or employee thereof, the Permittee shall defend, indemnify, and hold each of them harmless for such claim.
10. All backfill material is to be moistened as necessary and thoroughly compacted with mechanical means. If required by the County Director of Public Works, such backfill shall consist of gravel or crushed rock. The Permittee shall maintain the surface over structures placed hereunder as may be necessary to insure the return of the roadway to a completely stable condition and until relieved of such responsibility by the County Department of Public Works. Wherever a gravel, crushed rock or asphalt surface is removed or damaged in the course of work related to the permitted encroachment, such material shall either be separately stored and replaced in the roadway as nearly as possible in its original state or shall be replaced in kind, and the roadway shall be left in at least as good a condition as it was before the commencement of operations of placing the encroachment structure.
11. Whenever it becomes necessary to secure permission from abutting property owners for the proposed work, such authority must be secured by the Permittee prior to starting work.
12. The current and future safety and convenience of the traveling public shall be given every consideration in the location and methods of construction utilized.
13. The Permittee is responsible for the preservation of survey monuments located within the area of work herein permitted. Prior to the start of construction, survey monuments that potentially may be disturbed shall be located and referenced by a Licensed Land Surveyor, and a Corner Record filed with the County Surveyor. Any Survey Monuments disturbed during the course of construction shall be reestablished by a Licensed Land Surveyor and another Corner Record filed with the County Surveyor. (Land Surveyors' Act Section 8771)
14. Prior to any excavation, the Permittee shall notify USA North (Underground Service Alert of Northern California and Nevada) at 811 or 800-227-2600 forty-eight (48) hours in advance.

GENERAL PROVISIONS

GOVERNING INSTALLATION OF SUBSURFACE STRUCTURES AND PIPELINES WITHIN COUNTY ROAD RIGHTS-OF-WAY

PUBLIC CONVENIENCE AND SAFETY:

- A. Before obstructing any private driveway entrance or County road traveled way with a trench, spoil bank, equipment or other barrier permitted for any prolonged period of time, the Permittee shall notify the known users of the respective thoroughfare(s) involved, and shall provide access for vehicular and pedestrian traffic to and from the road.
 - 1. Unless otherwise permitted, all work shall be conducted in such a manner that no less than one lane of the existing County road traveled way will be maintained open to public traffic during working hours in a smooth and safe riding condition(s). Two lanes shall be open after working hours.
 - 2. In cases where road closure is permitted, the permission to close the road will be granted under the condition that the Permittee notify the following persons and/or agencies of the time, the period of closure, and the detour route at least twenty-four (24) hours prior to said road closure.
 - a. The County of San Joaquin Public Works Department
 - b. The County of San Joaquin Sheriff's Office
 - c. The local postal service
 - d. The local fire district
 - e. The local school district
 - f. The local residents involved
- B. Should hazardous conditions relative to the installation operations warrant flagmen, as many capable flagmen as may be necessary shall be provided by the Permittee and stationed in advance of work to warn and direct traffic.
- C. Lights, signs and barricades shall be furnished, erected and maintained by the Permittee for the adequate warning and convenience of the public, with particular attention to be taken in this regard after dark.
- D. Any excess dirt and/or debris which might be a hazard to either automobile or pedestrian traffic, uncontrollable by lights, signs and barricades, shall be removed from the jobsite daily.

STRUCTURES:

- A. Walls of structures shall be such quality and strength that they will resist all pressures and will not crack or be deformed in such a way as to create a hazard or maintenance problem at any time. Therefore, the minimum structural requirements for concrete pipe placed under county road rights-of-way shall conform to the following American Association of State Highway and transportation Officials (AASHTO) designations.
 - 1. For concrete pipe up to and including thirty-three inches (33") inside diameter, extra strength concrete conforming to AASHTO Designation M 170M.
 - 2. For concrete pipe thirty-six inches (36") inside diameter and larger, reinforced concrete pipe conforming to AASHTO Designation M 170M Class III.
 - 3. Plastic pipe conforming to AASHTO Designation M294.
- B. All concrete pipe joints with County road rights-of-way shall be sealed against leakage and/or infiltration with rubber gasket in conformance with Section 65-1:06 of the California Standard Specifications, or with other methods as may be permitted under the Special Provisions.
- C. Cast-in-place concrete pipe, vitrified clay pipe, spiral welded steel pipe, or corrugated aluminum alloy pipe shall not be installed within the County road rights-of-way unless specifically so stated in the Special Provisions, and only under the conditions as provided.
- D. All structures to be buried within the County rights-of-way shall be set at such elevations as to allow minimum coverage of thirty inches (30") to the centerline of the roadways and twelve inches (12") at the bottoms of borrow ditches each side of the roadways. The depths of structures shall be established below a flat plane extending across the rights-of-way, no part of which shall extend above the elevations stated above; manholes, lampholes, valves, etc. not included. Future surface elevations shall be anticipated as nearly as possible and structure elevations shall be established for future adjustments accordingly.
- E. The County hereby reserves the right to specify in the Special Provisions the gage and surface treatment of any galvanized corrugated metal pipe that is to be installed.
- F. All longitudinal utility facilities are to be established (and dimensioned on sketches) from surveyed centerline of road right-of-way, not from right-of-way (border) lines.

REPAIRS OF THE COUNTY RIGHT-OF-WAY:

- A. All excavations shall be backfilled and compacted immediately after work therein has been completed.
- B. Trenched shall not be left open farther than 300 feet in advance of pipe laying operations, or 200 feet to the rear thereof, unless otherwise permitted by the Engineer.
- C. Unless otherwise permitted under the Special Provisions, backfill shall be placed and mechanically compacted in such a manner that the relative compaction throughout the entire fill within the County road right-of-way shall conform to the percentages of compaction as shown on the Trench detail.
- D. Backfill material shall be placed in horizontal uniform layers not to exceed in thickness, before compaction, 0.67 foot in the bedding region, one-foot where 90% compaction is required, and two-feet where 80% compaction is required.
- E. No portion of the excavation(s) shall be compacted by ponding or jetting unless a maintenance bond is provided.
- F. Gravel backfill material shall be utilized only where specifically so stated on the face of the permit. It shall be compacted by means of a high-frequency internal vibrator, the compactor to be a size and type approved by the Engineer. Points of compaction shall not be greater than 18" centers and to the full depth of the lift.
- G. All pavements, curbs, gutters, sidewalks, borrow ditches, pipes, head walls, road signs, trees, shrubbery, and/or other permanent road facilities impaired by or as a result of construction operations at the construction site(s) occupied by materials and/or equipment, shall be restored immediately upon backfilling of the excavation to the original grades and cross sections, and to a condition as good as, or better than existing prior to construction.
- H. All surfacing materials of roadways and driveway approaches cut or damaged by or as a result of construction operations, shall be replaced within ONE WEEK following the backfilling of excavation, weather permitting, with compacted layers of surfacing materials at least as thick as the existing, and no less than two inches (2") of asphalt concrete over six inches (6") of aggregate base, both as specified below.
 - 1. Asphalt Concrete: Combined mineral aggregate shall conform to the quality and gradation requirements for Type "A" one-half inch (1/2) maximum aggregate, coarse or medium gradation as specified in Section 39 of the California Standard Specifications. The bituminous binder to be mixed with mineral aggregate shall be paving asphalt having (Grade PG 64-10), unless otherwise directed by the Engineer. Placement of asphalt concrete surfacing shall conform to the applicable provisions of Section 39 of the California Standard Specifications.
 - 2. Aggregate Base: Combined mineral aggregates shall conform to the quality and the grading for three-quarter inch (3/4") maximum size aggregate Class 2 Aggregate Base specified in Section 26 of the California Standard Specifications.
- I. Before acceptance of repairs to the County road rights-of-way, all unsightly and detrimental dirt, dust and/or debris shall be removed and the construction areas left in a neat and presentable condition(s).
 - 1. If necessary, County road traveled way and driveway pavements shall be washed with water to remove dirt and dust.
 - 2. Driveway approaches and field entrance pavements damaged by equipment or spoil banks shall be repaired as directed by the Engineer.
- J. Upon request by the County, any settlement, sagging of surface, or cracking of pavement shall be repaired immediately by and at the sole expense of the Permittee for a period of one year following acceptance of the work.

SPECIAL PROVISIONS

Winter Weather Utility Work

1. **SUPERVISION:** The utility company (**permittee**) shall furnish full-time supervision of all work to insure compliance with the permit provision.
2. **START OF WORK:** No work within the County right-of-way shall be started until the utility company representative has made an evaluation of weather conditions and has determined the work can be accomplished under the provisions of the permit.
3. **CLEAN PAVEMENT:** Dirt and mud shall not be deposited on the pavement outside the area of work, and if inadvertently tracked onto the road travel way shall be removed immediately.
4. **DAILY RESTORATION:** Private driveways and road intersections shall be restored daily.
5. **WEATHER-TIGHT CONDITIONS:** All trenches shall be filled and compacted, ditches and other drainage facilities regarded and opened, and the entire work area restored to weather-tight condition prior to any rain.

APPLICATION FOR ENCROACHMENT PERMIT

PLEASE PRINT:

Date 07/22/19

To: San Joaquin County
Department of Public Works

AT&T / VCC PERMITS DESK
(Applicant Name)

5555 E. Olive Ave
(Mailing Address)

Fresno, CA 93727
(City, State, Zip Code)

(559) 454-4900 g26977@att.com
(Area Code - Telephone Number)

OFFICE USE ONLY

JOB #	<u>730079</u>	REF #	
APN		CR #	
EXP. DATE			
VALID		TO	
STREET			DRIVEWAYS:
AREA		QUAD	*
TYPE			*
FORMS			*
NOTES			

Sketch (Detailed plans may be submitted)

A COPY OF THE TRAFFIC CONTROL PLAN IS SUBMITTED WITH THIS PERMIT;
SEE ATTACHMENTS

AOI MEOL

The undersigned hereby applies for permission to excavate, construct and/or otherwise encroach on County Highway Right-of-Way on the EAST side of HARLAN RD approximately 420' feet mile NORTH of ROTH RD, by performing the following work (description of work):
ACCESS MANHOLE# 2245 TO SPLICE EXISTING FIBER CABLE.

PLEASE SEE ATTACHED DOCUMENT FOR OTHER SPECIFIC JOB LOCATION & DESCRIPTION.

Work will commence on or about 8/15/19 for approximately 4 days.

I, the undersigned, certify that I am the owner of the respective property, or am qualified to represent the owner and agree to do the work described above in accordance with the rules and regulations of San Joaquin County and subject to inspection and approval.


Signature of Applicant - Title
Engineering
Administrator

07/22/2019
Date

PERMIT APPLICATION FOR AT&T JOB# A01ME0L

JOB LOCATION:

AERIAL: 10736 HARLAN RD

POLE LOC 3: 10736 HARLAN RD

JOB DESCRIPTION:


AERIAL: E/S HARLAN RD, 1,205' N/O ROTH RD, ACCESS (2) POLES TO PLACE AERIAL FIBER CABLE.

POLE LOC 3: E/S HARLAN RD, 1,220' N/O ROTH RD, PLACE (1) 3-ELECTRODE GROUND BED IN DIRT AT POLE LOC. 3.

THE ASSOCIATED TCP IS SUBMITTED WITH PERMIT. PLEASE SEE THE ATTACHED PERMIT DRAWINGS FOR AT&T JOB# A01ME0L.



SAN JOAQUIN
COUNTY
Greatness grows here.



AOIMEOL

Department of Public Works

Kris Balaji, Director of Public Works

Fritz Buchman, Deputy Director/Development

Michael Selling, Deputy Director/Engineering

Jim Stone, Deputy Director/Operations

Kristi Rhea, Manager of Strategic Initiatives

Acknowledgement of Monument Preservation

I, JAMES S. OAK, a duly Licensed Land Surveyor or a Professional Engineer
(Please print)

authorized to perform Land Surveying in the State of California, Registration No. L.S. 3718,

hereby acknowledge and accept all responsibility for the monument preservation as required

per Section 8771(a-f) of the Business and Professions Code within the bounds of the

construction activity permitted by San Joaquin County Permit No. _____.

I further acknowledge that I am hereby responsible for the Acknowledgement of Monument

Preservation prior to final acceptance of the construction activity.


James S. Oak
Signature

7-18-19
Date

PS-MONUMENT PRESERVATION

Seal





S.N.F. —

APPROX. 1220'
N. OF RDTH

SEARCHED,
NO. 102052

DEED REFERENCES: INSTRUMENT NO'S.
86 102052, 86 102053, 86 102054

SHIPPEE FRENCH CAMP TRACT
M.S.P. 3-31 S.D.C. RECORDS
(ref. e.)

(N 89° 47' 30" E. 993.6 ref. c.)
(N 89° 47' 30" E. 993.9 ref. d.)

FO. 1" PIPE (ref. c.)

SEARCHED, FD. NOTHING
SEARCHED, FD. NOTHING
SEARCHED, FD. NOTHING

MEAS. (N. 11° 54' E. 684.4 (ref. 2))
MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))
MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))
MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

E.S. 22-96

PRIVATE
ROADWAY AS SHOWN
(ref. e.)

LOT 18

LOT 19
FRENCH CAMP

8.73 AC.

PARCEL 1

HARLAN ROAD

SHIPPEE TRACT

W.E. 1 OF 1

(644.8' ref. c.)
20° 20' E
420.50'

1499.74' W
642.9'

FO. 1" PIPE

1500'

860.18'

285.5 (ref. 2)

857.10' MEAS.

N. 89° 44' W.

15.92'

420.23'

(N. 11° 54' E. 684.4 (ref. 2))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))



MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

MEAS. (S. 89° 47' 10" E. 1245.7 (ref. 4))

SHIPPEE FRENCH CAMP TRACT

THIS MAP IS FOR
ASSESSMENT
USE ONLY

193-27



The sole purpose of this document is for the assessment and taxation of County property taxes. County makes no representation or warranty, express or implied, about the accuracy, completeness, reliability or timeliness of the information contained herein. The information is provided for your information only and should not be used for any other purpose. The County is not responsible for any errors or omissions in this document or for any consequences arising therefrom or in connection with the use of or reliance upon this document.

A - P. M. Bk. 16 Pg. 059
C - R. S. Bk. 22 Pg. 036
D - R. M. Bk. 26 Pg. 059

HIGHEST A.P.N. USED		
YEAR	PAR. #	PAR. #
84-85	18	
85-86	18	
86-87	20	
87-88	21	
88-89		
89-90		
90-91		
91-92		
92-93		
93-94		
94-95		
95-96		
96-97		
97-98		
98-99		
99-00		
00-01		
01-02		
02-03		
03-04		
04-05		
05-06		
06-07		
07-08		
08-09		
09-10		
10-11		
11-12		
12-13		
13-14		
14-15		
15-16		
16-17		
17-18		
18-19		
19-20		
20-21		
21-22		
22-23		
23-24		
24-25		
25-26		
26-27		
27-28		
28-29		
29-30		
30-31		
31-32		
32-33		
33-34		
34-35		
35-36		
36-37		
37-38		
38-39		
39-40		
40-41		
41-42		
42-43		
43-44		
44-45		
45-46		
46-47		
47-48		
48-49		
49-50		
50-51		
51-52		
52-53		
53-54		
54-55		
55-56		
56-57		
57-58		
58-59		
59-60		
60-61		
61-62		
62-63		
63-64		
64-65		
65-66		
66-67		
67-68		
68-69		
69-70		
70-71		
71-72		
72-73		
73-74		
74-75		
75-76		
76-77		
77-78		
78-79		
79-80		
80-81		
81-82		
82-83		
83-84		
84-85		
85-86		
86-87		
87-88		
88-89		
89-90		
90-91		
91-92		
92-93		
93-94		
94-95		
95-96		
96-97		
97-98		
98-99		
99-00		
00-01		
01-02		
02-03		
03-04		
04-05		
05-06		
06-07		
07-08		
08-09		
09-10		
10-11		
11-12		
12-13		
13-14		
14-15		
15-16		
16-17		
17-18		
18-19		
19-20		
20-21		
21-22		
22-23		
23-24		
24-25		
25-26		
26-27		
27-28		
28-29		
29-30		
30-31		
31-32		
32-33		
33-34		
34-35		
35-36		
36-37		
37-38		
38-39		
39-40		
40-41		
41-42		
42-43		
43-44		
44-45		
45-46		
46-47		
47-48		
48-49		
49-50		
50-51		
51-52		
52-53		
53-54		
54-55		
55-56		
56-57		
57-58		
58-59		
59-60		
60-61		
61-62		
62-63		
63-64		
64-65		
65-66		
66-67		
67-68		
68-69		
69-70		
70-71		
71-72		
72-73		
73-74		
74-75		
75-76		
76-77		
77-78		
78-79		
79-80		
80-81		
81-82		
82-83		
83-84		
84-85		
85-86		
86-87		
87-88		
88-89		
89-90		
90-91		
91-92		
92-93		
93-94		
94-95		
95-96		
96-97		
97-98		
98-99		
99-00		
00-01		
01-02		
02-03		
03-04		
04-05		
05-06		
06-07		
07-08		
08-09		
09-10		
10-11		
11-12		
12-13		
13-14		
14-15		
15-16		
16-17		
17-18		
18-19		
19-20		
20-21		
21-22		
22-23		
23-24		
24-25		
25-26		
26-27		
27-28		
28-29		
29-30		
30-31		
31-32		
32-33		
33-34		
34-35		
35-36		
36-37		
37-38		
38-39		
39-40		
40-41		
41-42		
42-43		
43-44		
44-45		
45-46		
46-47		
47-48		
48-49		
49-50		
50-51		
51-52		
52-53		
53-54		
54-55		
55-56		
56-57		
57-58		
58-59		
59-60		
60-61		
61-62		
62-63		
63-64		
64-65		
65-66		
66-67		
67-68		
68-69		
69-70		
70-71		
71-72		
72-73		
73-74		
74-75		
75-76		
76-77		
77-78		
78-79		
79-80		
80-81		
81-82		
82-83		
83-84		
84-85		
85-86		
86-87		
87-88		
88-89		
89-90		
90-91		
91-92		
92-93		
93-94		
94-95		
95-96		
96-97		
97-98		
98-99		
99-00		
00-01		
01-02		
02-03		
03-04		
04-05		
05-06		
06-07		
07-08		
08-09		
09-10		
10-11		
11-12		
12-13		
13-14		
14-15		
15-16		
16-17		
17-18		
18-19		
19-20		
20-21		
21-22		
22-23		
23-24		
24-25		
25-26		
26-27		
27-28		
28-29		
29-30		
30-31		
31-32		
32-33		
33-34		
34-35		
35-36		
36-37		
37-38		
38-39		
39-40		
40-41		
41-42		
42-43		
43-44		
44-45		
45-46		
46-47		
47-48		
48-49		
49-50		
50-51		
51-52		
52-53		
53-54		
54-55		
55-56		
56-57		
57-58		
58-59		
59-60		
60-61		
61-62		
62-63		
63-64		
64-65		
65-66		
66-67		
67-68		
68-69		
69-70		
70-71		
71-72		
72-73		
73-74		
74-75		
75-76		
76-77		
77-78		
78-79		
79-80		
80-81		
81-82		
82-83		
83-84		
84-85		
85-86		
86-87		
87-88		
88-89		
89-90		
90-91		
91-92		
92-93		
93-94		
94-95		
95-96		
96-97		
97-98		
98-99		
99-00		
00-01		
01-02		
02-03		
03-04		
04-05		
05-06		
06-07		
07-08		
08-09		
09-10		
10-11		
11-12		
12-13		
13-14		
14-15		
15-16		
16-17		
17-18		
18-19		
19-20		
20-21		
21-22		
22-23		
23-24		
24-25		
25-26		
26-27		
27-28		
28-29		
29-30		
30-31		
31-32		
32-33		
33-34		
34-35		
35-36		
36-37		
37-38		
38-39		
39-40		
40-41		
41-42		
42-43		
43-44		
44-45		
45-46		
46-47		
47-48		
48-49		
49-50		
50-51		
51-52		
52-53		
53-54		
54-55		
55-56		
56-57		
57-58		
58-59		
59-60		
60-61		
61-62		
62-63		
63-64		
64-65		
65-66		
66-67		
67-68		
68-69		
69-70		
70-71		
71-72		
72-73		
73-74		
74-75		
75-76		
76-77		
77-78		
78-79		
79-80		
80-81		
81-82		
82-83		
83-84		
84-85		
85-86		
86-87		
87-88		
88-89		
89-90		
90-91		
91-92		
92-93		
93-94		
94-95		
95-96		
96-97		
97-98		
98-99		
99-00		
00-01		
01-02		
02-03		
03-04		
04-05		
05-06		
06-07		
07-08		
08-09		
09-10		
10-11		
11-12		
12-13		
13-14		
14-15		
15-16		
16-17		
17-18		
18-19		
19-20		
20-21		
21-22		
22-23		
23-24		
24-25		
25-26		
26-27		
27-28		
28-29		
29-30		
30-31		
31-32		
32-33		
33-34		
34-35		
35-36		
36-37		
37-38		
38-39		
39-40		
40-41		
41-42		
42-43		
43-44		




EXCAVATION DATA

OWNER	ASPHALT	CONCRETE	DIRT
SAN JOAQUIN COUNTY	N/A	NA	18'X1' =18 SQ FT

PLACE (1) 3-ELECTRODE GROUND BED IN
DIRT @ LOC 3 (37°51'33.8"N 121°16'49.5"W)

DIG ALERT
BEFORE EXCAVATING CALL
U.G. SERVICE ALERT
1-800-227-2600
CALL 2 FULL WORKING DAYS
IN ADVANCE




- CONSTRUCTION NOTES:**
- 1.MINIMUM COVER FOR STRUCTURE IS 30" BELOW GUTTER FLOW LINE OR 36" BELOW EXISTING GRADE, WHICH EVER IS GREATER.
 - 2.ALL SUBSTRUCTURE INFORMATION SHOWN WAS TAKEN FROM RECORDS AVAILABLE AND IS APPROXIMATE. VERIFY, LOCATE AND PROTECT AS REQUIRED.
 - 3.ALL TRAFFIC CONTROL TO BE IN ACCORDANCE WITH THE 2014 WORK AREA TRAFFIC CONTROL HANDBOOK AND CALIFORNIA M.U.T.C.D.
 4. CONSTRUCTION TO UTILIZE AND IMPLEMENT ALL BEST MANAGEMENT PRACTICES (BMP'S) AS REQUIRED TO ENSURE COMPLIANCE WITH THE SBC POLICY LETTER ISSUED FEBRUARY 21, 2003 BY ENVIRONMENTAL MANAGEMENT CONCERNING STORM WATER PERMITTING AND STORM WATER POLLUTION PREVENTION PLANS (SWPPP) AND IN ACCORDANCE WITH THE CLEAN WATER ACT (1965) AND EPA REGULATIONS PUBLISHED 1990 AS MODIFIED BY THE PHASE II RULE, IN 1999.

- 46L CONSTRUCTION NOTES:**
1. EXCAVATE & PLACE 3-ELECTRODE GROUND BED IN DIRT @ LOC. 3
 2. GROUND BEDS SHALL BE INSTALLED WITH A MINIMUM HORIZONTAL/PARALLEL SEPARATION OF 5 FT FROM EXISTING WATER FACILITIES.


GEO/CO: UE76
TELEPHONE: (559) 739-6646
TYPE OF CONST:
PLACE GND BED
JOB NO: A01ME0L
DWG 1 OF 1



NOT TO SCALE




GROUND BED PROFILE TYPICAL




NOT TO SCALE

GROUND BED
CROSS SECTIONAL DIAGRAM




NOT TO SCALE

SIGN LEGEND




ROAD WORK AHEAD

W20-1




ROAD CLOSED AHEAD

W20-3




DETOUR AHEAD

W20-2




RIGHT LANE CLOSED AHEAD

C20(CA)(R)




LEFT LANE CLOSED AHEAD

C20(CA)(L)




CENTER LANE CLOSED AHEAD

W9-3




BIKE LANE CLOSED AHEAD

C20(CA)(BIKE)




LANE CLOSED

W4-2(R)
W4-2(L)




BIKE LANE CLOSED

C30 (CA)




ONE LANE ROAD AHEAD

C30(BIKE)




W20-4




BE PREPARED TO STOP

W3-4




RAMP CLOSED AHEAD

W20-3




SPEED LIMIT 35

W3-5




NARROW LANE

C12(CA)




ROAD NARROWS

W5-1




YIELD

W12-1




MERGE

W6-3




LEFT TURN

W1-4(L)
W1-4(R)




RIGHT TURN

W4-1




PEDESTRIAN CROSSING

W21-1a




BIKE CROSSING

C9A (CA)




OPEN TRENCH

C27(CA)




BIKE CROSSING

W11-1




SHOULDER WORK

W21-5




RIGHT SHOULDER CLOSED AHEAD

W21-5bR




RIGHT SHOULDER CLOSED 1000 FT

W21-5b




SHOULDER CLOSED

C30A




NO LEFT TURN

R3-1




NO RIGHT TURN

R3-2




NO U-TURN

R3-4




NO LEFT TURN

R3-18




NO BICYCLES

R5-6




NO PEDESTRIANS

R9-3




STOP

R1-1




YIELD

R1-2




DO NOT ENTER

R5-1




SLOW

SLOW PADDLE




RIGHT LANE MUST TURN RIGHT

R3-7(R)




LEFT LANE MUST TURN LEFT

R3-7(L)




ROAD CLOSED

R11-2




RAMP CLOSED

R11-2




ROAD CLOSED TO THRU TRAFFIC

R11-4




BEGIN RIGHT TURN LANE

R4-4




SHARE THE ROAD

W16-1P




MAY USE FULL LANE

R4-11




BUSES ONLY

SPCL




KEEP RIGHT

R4-7a




KEEP LEFT

R4-8a




RIGHT TURN

R3-6(R)




LEFT TURN

R4-7




RIGHT TURN

R4-8




ONLY

R3-5R




YIELD

R60B(CA)




SIDEWALK CLOSED

R9-9




SIDEWALK CLOSED AHEAD

R9-11(L)
R9-11(R)




SIDEWALK CLOSED

R9-11a(L)
R9-11a(R)




SIDEWALK CLOSED

R9-10




END ROAD WORK

G20-2




RIGHT TURN

W1-6(R)
W1-6(L)




LEFT TURN

W1-7




DETOUR

SC3 (CA)




END DETOUR

M4-8a




DETOUR

M4-9(L)
M4-9(R)
M4-9(S)




NO LEFT TURN

R13A



NO RIGHT TURN


R13B




DO NOT STOP ON TRACKS

R8-8


SYMBOL LEGEND




CHANNELIZING DEVICE/CONE




CHANNELIZING DEVICE W/ SIGN




TYPE I BARRICADE W/ SIGN




EXISTING SIGN




SIGNALIZED INTERSECTION




TYPE III BARRICADE W/SIGN(5'H x 4'W)




TYPE II BARRICADE W/SIGN(3'H x 2'W)




HIGH LEVEL WARNING DEVICE




FLASHING ARROWBOARD




T.A.N.S.A.T.




TYPE III BARRICADE




TYPE II BARRICADE




CERTIFIED FLAGGER




PORTABLE FLASHING BEACON




T.A.N.S.




AERIAL CABLE




SPLICE BOX




EXISTING STRIPING DOUBLE YELLOW




EXISTING STRIPING




CHANGEABLE MESSAGE SIGN (CMS)




TRENCHING




HAND HOLE




BORE PIT




POWER POLE




MANHOLE




EXISTING DRIVEWAY




WORK ZONE (ACTIVITY AREA)



DIRECTION OF TRAVEL



EXISTING LANE FLOW STRIPING



WORK VEHICLE

GENERAL TRAFFIC CONTROL NOTES:

1. THE CONTRACTOR IS RESPONSIBLE FOR PROMPTLY RESTORING THE ROAD BACK TO SATISFACTORY CONDITION WHICH INCLUDES, BUT IS NOT LIMITED TO, PAVING, STRIPING, MARKINGS, SIGNAGE, AND LOOP DETECTION. ALL PLANS SHALL BE IN ACCORDANCE WITH 2014 CAMUTCD.
2. THE AGENCY RESERVES THE RIGHT TO OBSERVE THESE TRAFFIC CONTROL PLANS IN OPERATION AND TO MAKE CHANGES AS FIELD CONDITIONS WARRANT.
3. TRENCHES SHALL BE BACKFILLED OR STEEL-PLATED DURING NON-WORK HOURS. STEEL PLATES SHALL HAVE AN ASPHALT RAMP ON ALL EDGES, SECURELY SUPPORTED SO THEY WON'T ROCK AND A SIGN POSTED NEAR THE PLATES IDENTIFYING THE CONTRACTOR'S NAME AND 24 HOUR EMERGENCY TELEPHONE NUMBER. ALL DIRT, DUST, AND DEBRIS SHALL BE REMOVED FROM THE STREET AT THE END OF EACH DAY AND AT THE END OF THE JOB. THE STREET SHALL BE KEPT IN A DRIVABLE CONDITION AT ALL TIMES.
4. ANY WORK THAT CREATES AN UNDUE SAFETY RISK OR THAT CREATES SEVERE CONGESTION WILL BE SHUT DOWN BY THE AGENCY.
5. A COPY OF ALL TRAFFIC REQUIREMENTS AND TRAFFIC CONTROL PLANS ISSUED BY THE AGENCY MUST BE KEPT ON THE JOB SITE.
6. APPROVAL OF THIS PLAN DOES NOT CONSTITUTE AN OFFICIAL PERMIT. CONTACT THE AGENCY FOR INFORMATION ON OBTAINING A PERMIT.
7. ALL TRAVEL LANES WILL TYPICALLY BE A MINIMUM OF 12 FEET WIDE, 14 FEET IF ADJACENT TO BIKE LANES, UNLESS OTHERWISE SPECIFICALLY APPROVED BY THE AGENCY.
8. FLASHING ARROW BOARDS AS REQUIRED BY THE AGENCY.
9. WARNING (W) SERIES SIGNS USED IN WORK ZONES SHALL BE BLACK ON AN ORANGE BACKGROUND.
10. CONES AND PYLONS SHALL HAVE YELLOW REFLECTORIZED SLEEVES WHEN PLACED ALONG THE CENTERLINE AND WHITE REFLECTORIZED SLEEVES ALONG THE OUTSIDE SHOULDER.
11. IF PARKING IS ALLOWED IN THE ADVANCE WORKING AREA, ADVANCE WARNING SIGNS SHALL BE MOUNTED ON HIGH LEVEL DEVICES.
12. THE CONTRACTOR SHALL POST TOW-AWAY/NO PARKING SIGNS SEVENTY-TWO (72) HOURS IN ADVANCE, WITH DAY OF WEEK, DATE, AND WORK HOURS NOTED, AND SHALL BAG PARKING METERS (WHERE APPLICABLE).
13. OPEN CUT WORK SHALL BE DONE IN __ PHASES.
14. WORKERS SHALL WEAR HARD HATS AND ORANGE VESTS AT ALL TIMES.
15. COUNTY TRANSIT DISTRICT SHALL BE NOTIFIED (5) WORKING DAYS PRIOR TO ANY WORK THAT AFFECTS BUS STOPS.
16. CONSTRUCTION SIGNS SHALL NOT OBSTRUCT SIGHT VISIBILITY AT DRIVEWAYS.
17. CONTRACTOR SHALL NOTIFY ALL LOCAL BUSINESS OWNERS/OCCUPANTS 72 HOURS IN ADVANCE PRIOR TO ANY CONSTRUCTION ADJACENT TO BUSINESSES.

JOB LOCATION:

HARLAN RD.

WORK HOURS:

FROM:

TO:

BEGIN CROSS STREET:

ROTH RD.

END CROSS STREET:

E TRANSPORTATION CT.

PERMIT NUMBER:

THOMAS GUIDE:

SCOPE OF WORK:

MANHOLE & POLE ACCESS

START DATE:

END DATE:

PERMIT WORK EXTENSIONS MUST BE OBTAINED BY THE

END OF PERMIT DATE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	CONE SPACING	SIGN SPACING
45 MPH	45 MPH	180 FT	45 FT	350 FT
TRAFFIC CONTROL PLAN DISCLOSURE:				
NOTHING CONTAINED ON THIS DRAWING SHALL PREVENT LOCAL JURISDICTIONS FROM MODIFYING, CHANGING, OR ADOPTING NEW SPECIFICATIONS DEEMED NECESSARY.				
CRITERIA FOR POSITION, LOCATION, AND USE OF TRAFFIC CONTROL DEVICES IS SOLELY FOR THE PURPOSE OF GUIDANCE TO ASSIST IN THE SET UP OF THE TRAFFIC CONTROL PLANS.				
APPROVAL OF THIS PLAN DOES NOT CONSTITUTE AN OFFICIAL PERMIT. CONTACT THE AGENCY FOR INFORMATION ON OBTAINING A PERMIT.				

PLANS ACCEPTED BY:

R.C.E.

DATE

EXP. DATE

CHC Consulting

1845 W. Orangewood Ave., Suite 300, Orange, CA 92868

(949) 250-0004 / FAX (949) 250-0006

PLANS PREPARED BY:

NAME: VINEET

PHONE: (949) 250-0004

DATE: 07-01-19 REVISION DATE: N/A

JOB NUMBER

A01ME0L

SCALE: N/A

PAGE: COVER SHEET



-TABLE 6C-1 2014 CALIFORNIA MUTCD-
-RECOMMENDED ADVANCE WARNING SIGN SPACING-

ROAD TYPE	DISTANCE BETWEEN SIGNS**		
	A	B	C
URBAN - 25 MPH OR LESS***	100 FEET	100 FEET	100 FEET
URBAN - MORE THAN 25 MPH TO 40 MPH***	250 FEET	250 FEET	250 FEET
URBAN - MORE THAN 40 MPH***	350 FEET	350 FEET	350 FEET
RURAL	500 FEET	500 FEET	500 FEET
EXPRESSWAY/FREEWAY	1,000 FEET	1,500 FEET	2,640 FEET

** THE COLUMN HEADING A, B, AND C ARE THE DIMENSIONS SHOWN IN FIGURES 6H-1 THROUGH 6H-46. THE A DIMENSION IS THE DISTANCE FROM THE TRANSITION OR POINT OF RESTRICTION TO THE FIRST SIGN. THE B DIMENSION IS THE DISTANCE BETWEEN THE FIRST AND SECOND SIGNS. THE C DIMENSION IS THE DISTANCE BETWEEN THE SECOND AND THIRD SIGN. (THE "FIRST SIGN" IS THE SIGN IN A THREE-SIGN SERIES THAT IS CLOSEST TO TTC ZONE. THE "THIRD SIGN" IS THE SIGN THAT IS FURTHEST UPSTREAM FROM THE TTC ZONE.)
*** POSTED SPEED LIMIT, OFF-PEAK 85TH-PERCENTILE SPEED PRIOR TO WORK STARTING, OR OTHER ANTICIPATED OPERATING SPEED IN MPH

-TABLE 6C-2 2014 CALIFORNIA MUTCD-
-STOPPING SIGHT DISTANCE AS A FUNCTION OF SPEED ON LEVEL ROADS-
(USED AS SUGGESTED LONGITUDINAL BUFFER SPACE LENGTH OR LOCATION FOR FLAGGER STATION)

SPEED* (MPH)	DISTANCE (FT)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

* POSTED SPEED, OFF-PEAK 85TH-PERCENTILE SPEED PRIOR TO WORK STARTING OR THE ANTICIPATED OPERATING SPEED IN MPH

-TABLE 6C-3 2014 CALIFORNIA MUTCD-
-TAPER LENGTH CRITERIA FOR
TEMPORARY TRAFFIC CONTROL ZONE-

TYPE OF TAPER	TAPER LENGTH (L)*
MERGING TAPER	AT LEAST L
SHIFTING TAPER	AT LEAST 0.5 L
SHOULDER TAPER	AT LEAST 0.33 L
ONE LANE, TWO-WAY TRAFFIC TAPER	SOFT MINIMUM, 100FT MAXIMUM
DOWNSTREAM TAPER	SOFT MINIMUM, 100FT MAXIMUM

-TABLE 6C-4 2014 CALIFORNIA MUTCD-
-FORMULAS FOR DETERMINING TAPER LENGTH-


SPEED LIMIT (S)	TAPER LENGTH (L) FEET
40 MPH OR LESS	L= WS ²
45 MPH OR MORE	L= WS

WHERE: L= TAPER LENGTH IN METERS (FEET)
W= WIDTH OF OFFSET IN METERS (FEET)
S= POSTED SPEED LIMIT, OR OFF-PEAK 85TH-PERCENTILE SPEED PRIOR TO WORK STARTING, OR THE ANTICIPATED OPERATING SPEED IN KM/H (MPH)

COUNTY OF: SAN JOAQUIN


TRAFFIC CONTROL PLAN

HARLAN RD. & ROTH RD.
-MH #2245 ACCESS
WORK AREA 1 OF 2
UNDERGROUND



CONTACT PROPERTY OWNER(S) 72 HOURS PRIOR TO START OF WORK.

ALL TRAFFIC DEVICES WITHIN CITY OF LATHROP JOAQUIN RIGHT OF WAY SHALL BE APPROVED BY CITY OF LATHROP.



- LEGEND**
- = PORTABLE FLASHING BEACON (P.F.B.)
 - = TYPE III BARRICADE W/SIGN (5'H x 4'W)
 - = TYPE II BARRICADE W/SIGN (3'H x 2'W)
 - = 28" (11cm) TRAFFIC CONES W/ 13" (5cm) REFLECTIVE SLEEVE FOR DAY/NIGHT USE OR DELINEATORS IF DAY USE ONLY
 - = TRAFFIC CONE WITH CLIP ON SIGN
 - = TYPE I W/ SIGN
 - = EXISTING SIGN
 - = SIGNALIZED INTERSECTION
 - = FLASHING ARROWBOARD
 - = HIGH LEVEL WARNING DEVICE (FLAGTREE)
 - = FLAGGER
 - = TOW AWAY NO STOPPING ANY TIME
 - = EXISTING DRIVEWAY
 - = WORK ZONE (ACTIVITY AREA) LIMITS
 - = DIRECTION OF TRAFFIC




MAINTAIN DRIVEWAY ACCESS AT ALL TIMES

PHASE 1 OF 1	
TYPE OF CONSTRUCTION: MH #2245 ACCESS	
JOB NUMBER: A01ME0L	
PAGE: TC-1 OF TC-2	SCALE: 1:50


*HARLAN RD. & ROTH RD.
-POLE ACCESS
WORK AREA 2 OF 2
UNDERGROUND*

















ISSUE	DATE
1	07-01-19



LOCATION MAP



- ### LEGEND

- | | |
|---|---|
|  | = PORTABLE FLASHING BEACON (P.F.B.) |
|  | = TYPE III BARRICADE W/SIGN (5'H x 4'W) |
|  | = TYPE II BARRICADE W/SIGN (3'H x 2'W) |
|  | = 28" (11cm) TRAFFIC CONES W/ 13" (5cm) REFLECTIVE SLEEVE
FOR DAY/NIGHT USE OR DELINEATORS IF DAY USE ONLY |
|  | = TRAFFIC CONE WITH CLIP ON SIGN |
|  | = TYPE I W/ SIGN |
|  | = EXISTING SIGN |
|  | = SIGNALIZED INTERSECTION |
|  | = FLASHING ARROWBOARD |
|  | = HIGH LEVEL WARNING DEVICE (FLAGTREE) |
|  | = FLAGGER |
| TANSAT | = TOW AWAY NO STOPPING ANY TIME |
|  | = EXISTING DRIVEWAY |
|  | = WORK ZONE (ACTIVITY AREA) LIMITS |
|  | = DIRECTION OF TRAFFIC |



**MAINTAIN DRIVEWAY ACCESS
AT ALL TIMES**


PHASE 1 OF 1

TYPE OF CONSTRUCTION:
POLE ACCESS

JOB NUMBER: A01ME0L


PAGE: TC-2 OF TC-2	SCALE: 1:50
--------------------	----------------

SIGN LEGEND




ROAD WORK AHEAD

W20-1




ROAD CLOSED AHEAD

W20-3




DETOUR AHEAD

W20-2




RIGHT LANE CLOSED AHEAD

C20(CA)(R)




LEFT LANE CLOSED AHEAD

C20(CA)(L)




CENTER LANE CLOSED AHEAD

W9-3




BIKE LANE CLOSED AHEAD

C20(CA)(BIKE)




LANE CLOSED

W4-2(R)
W4-2(L)




BIKE LANE CLOSED

C30(CA)




ONE LANE ROAD AHEAD

C30(BIKE)




W20-4




BE PREPARED TO STOP

W3-4




RAMP CLOSED AHEAD

W20-3




SPEED LIMIT 35

W3-5




NARROW LANE

C12(CA)




ROAD NARROWS

W5-1




YIELD

W12-1




MERGE

W6-3




LEFT TURN

W1-4(L)
W1-4(R)




RIGHT TURN

W4-1




PEDESTRIAN CROSSING

W21-1a




BIKE CROSSING

C9A (CA)




OPEN TRENCH

C27(CA)




BICYCLE CROSSING

W11-1




SHOULDER WORK

W21-5




RIGHT SHOULDER CLOSED AHEAD

W21-5bR




RIGHT SHOULDER CLOSED 1000 FT

W21-5b




SHOULDER CLOSED

C30A




NO RIGHT TURN

R3-1




NO LEFT TURN

R3-2




NO U-TURN

R3-4




NO RIGHT TURN ON RED

R3-18




NO BICYCLES

R5-6




NO PEDESTRIANS

R9-3




STOP

R1-1




YIELD

R1-2




DO NOT ENTER

R5-1




SLOW

SLOW PADDLE




RIGHT LANE MUST TURN RIGHT

R3-7(R)




LEFT LANE MUST TURN LEFT

R3-7(L)




ROAD CLOSED

R11-2




RAMP CLOSED

R11-2




ROAD CLOSED TO THRU TRAFFIC

R11-4




BEGIN RIGHT TURN LANE

R4-4




SHARE THE ROAD

W16-1P




BIKES MAY USE FULL LANE

R4-11




BUSES ONLY

SPCL




KEEP RIGHT

R4-7a




KEEP LEFT

R4-8a




RIGHT TURN

R3-6(R)
R3-6(L)




LEFT TURN

R4-7




U-TURN

R4-8




ONLY

R3-5R




YIELD

R60B(CA)




SIDEWALK CLOSED

R9-9




SIDEWALK CLOSED AHEAD

R9-11(L)
R9-11(R)




SIDEWALK CLOSED

R9-11a(L)
R9-11a(R)




SIDEWALK CLOSED

R9-10




END ROAD WORK

G20-2




DETOUR

W1-6(R)
W1-6(L)




DETOUR

W1-7




DETOUR

SC3 (CA)




DETOUR

M4-8a




DETOUR

M4-9(L)
M4-9(R)
M4-9(S)




DETOUR

M4-10(L)
M4-10(R)




NO RIGHT TURN ON RED

R13A



NO LEFT TURN ON RED


R13B




DO NOT STOP ON TRACKS

R8-8


SYMBOL LEGEND




CHANNELIZING DEVICE/CONE




CHANNELIZING DEVICE W/ SIGN




TYPE I BARRICADE W/ SIGN




EXISTING SIGN




SIGNALIZED INTERSECTION




TYPE III BARRICADE W/SIGN(5'H x 4'W)




TYPE II BARRICADE W/SIGN(3'H x 2'W)




HIGH LEVEL WARNING DEVICE




FLASHING ARROWBOARD




T.A.N.S.A.T.




TYPE III BARRICADE




TYPE II BARRICADE




CERTIFIED FLAGGER




PORTABLE FLASHING BEACON




T.A.N.S.




AERIAL CABLE




SPLICE BOX




EXISTING STRIPING DOUBLE YELLOW




EXISTING STRIPING




CMS




TRENCHING




HAND HOLE




BORE PIT




POWER POLE




MANHOLE




EXISTING DRIVEWAY




WORK ZONE (ACTIVITY AREA)



DIRECTION OF TRAVEL



EXISTING LANE FLOW STRIPING



WORK VEHICLE

GENERAL TRAFFIC CONTROL NOTES:

1. THE CONTRACTOR IS RESPONSIBLE FOR PROMPTLY RESTORING THE ROAD BACK TO SATISFACTORY CONDITION WHICH INCLUDES, BUT IS NOT LIMITED TO, PAVING, STRIPING, MARKINGS, SIGNAGE, AND LOOP DETECTION. ALL PLANS SHALL BE IN ACCORDANCE WITH 2014 CAMUTCD.

2. THE AGENCY RESERVES THE RIGHT TO OBSERVE THESE TRAFFIC CONTROL PLANS IN OPERATION AND TO MAKE CHANGES AS FIELD CONDITIONS WARRANT.

3. TRENCHES SHALL BE BACKFILLED OR STEEL-PLATED DURING NON-WORK HOURS. STEEL PLATES SHALL HAVE AN ASPHALT RAMP ON ALL EDGES, SECURELY SUPPORTED SO THEY WON'T ROCK AND A SIGN POSTED NEAR THE PLATES IDENTIFYING THE CONTRACTOR'S NAME AND 24 HOUR EMERGENCY TELEPHONE NUMBER. ALL DIRT, DUST, AND DEBRIS SHALL BE REMOVED FROM THE STREET AT THE END OF EACH DAY AND AT THE END OF THE JOB. THE STREET SHALL BE KEPT IN A DRIVABLE CONDITION AT ALL TIMES.

4. ANY WORK THAT CREATES AN UNDUE SAFETY RISK OR THAT CREATES SEVERE CONGESTION WILL BE SHUT DOWN BY THE AGENCY.

5. A COPY OF ALL TRAFFIC REQUIREMENTS AND TRAFFIC CONTROL PLANS ISSUED BY THE AGENCY MUST BE KEPT ON THE JOB SITE.

6. APPROVAL OF THIS PLAN DOES NOT CONSTITUTE AN OFFICIAL PERMIT. CONTACT THE AGENCY FOR INFORMATION ON OBTAINING A PERMIT.

7. ALL TRAVEL LANES WILL TYPICALLY BE A MINIMUM OF 12 FEET WIDE, 14 FEET IF ADJACENT TO BIKE LANES, UNLESS OTHERWISE SPECIFICALLY APPROVED BY THE AGENCY.

8. FLASHING ARROW BOARDS AS REQUIRED BY THE AGENCY.

9. WARNING (W) SERIES SIGNS USED IN WORK ZONES SHALL BE BLACK ON AN ORANGE BACKGROUND.

10. CONES AND PYLONS SHALL HAVE YELLOW REFLECTORIZED SLEEVES WHEN PLACED ALONG THE CENTERLINE AND WHITE REFLECTORIZED SLEEVES ALONG THE OUTSIDE SHOULDER.

11. IF PARKING IS ALLOWED IN THE ADVANCE WORKING AREA, ADVANCE WARNING SIGNS SHALL BE MOUNTED ON HIGH LEVEL DEVICES.

12. THE CONTRACTOR SHALL POST TOW-AWAY/NO PARKING SIGNS SEVENTY-TWO (72) HOURS IN ADVANCE, WITH DAY OF WEEK, DATE, AND WORK HOURS NOTED, AND SHALL BAG PARKING METERS (WHERE APPLICABLE).

13. OPEN CUT WORK SHALL BE DONE IN __ PHASES.

14. WORKERS SHALL WEAR HARD HATS AND ORANGE VESTS AT ALL TIMES.

15. COUNTY TRANSIT DISTRICT SHALL BE NOTIFIED (5) WORKING DAYS PRIOR TO ANY WORK THAT AFFECTS BUS STOPS.

16. CONSTRUCTION SIGNS SHALL NOT OBSTRUCT SIGHT VISIBILITY AT DRIVEWAYS.

17. CONTRACTOR SHALL NOTIFY ALL LOCAL BUSINESS OWNERS/OCCUPANTS 72 HOURS IN ADVANCE PRIOR TO ANY CONSTRUCTION ADJACENT TO BUSINESSES.

JOB LOCATION:
10736 HARLAN RD.

BEGIN CROSS STREET:
ROTH RD.

PERMIT NUMBER:

SCOPE OF WORK:
GB PL.

START DATE:

END DATE:

PERMIT WORK EXTENSIONS MUST BE OBTAINED BY THE
END OF PERMIT DATE

WORK HOURS:
FROM:
TO:

END CROSS STREET:
E TRANSPORTATION CT.

THOMAS GUIDE:

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	CONE SPACING	SIGN SPACING
45 MPH	45 MPH	180 FT	45 FT	350 FT
TRAFFIC CONTROL PLAN DISCLOSURE:				
NOTHING CONTAINED ON THIS DRAWING SHALL PREVENT LOCAL JURISDICTIONS FROM MODIFYING, CHANGING, OR ADOPTING NEW SPECIFICATIONS DEEMED NECESSARY.				
CRITERIA FOR POSITION, LOCATION, AND USE OF TRAFFIC CONTROL DEVICES IS SOLELY FOR THE PURPOSE OF GUIDANCE TO ASSIST IN THE SET UP OF THE TRAFFIC CONTROL PLANS.				
APPROVAL OF THIS PLAN DOES NOT CONSTITUTE AN OFFICIAL PERMIT. CONTACT THE AGENCY FOR INFORMATION ON OBTAINING A PERMIT.				

TRAFFIC CONTROL PLAN

PLANS ACCEPTED BY:

R.C.E.

EXP. DATE

CHC Consulting


1845 W. Orangewood Ave., Suite 300, Orange, CA 92868
(949) 250-0004 / FAX (949) 250-0006

PLANS PREPARED BY:
NAME: ANMOL GUJRAL
PHONE: (949) 250-0004
DATE: 07-05-19 REVISION DATE: N/A



JOB NUMBER A01ME0L


SCALE: N/A

PAGE: COVER SHEET



HARLAN RD. & ROTH RD.
-GB PL.
WORK AREA 1 OF 1
UNDERGROUND





MAINTAIN DRIVEWAY ACCESS AT ALL TIMES

PHASE 1 OF 1

TYPE OF CONSTRUCTION:
GB PL.

JOB NUMBER: A01ME0L

PAGE: TC-1 OF TC-1

SCALE: 1:40